

Date: 11th APRIL 2024

TENDER ADVERTISEMENT

Habitat for Humanity Kenya invites bids from interested, eligible, reputable, and competent suppliers for the supply of:

TENDER REF NO	ITEM DESCRIPTION	LOCATION
HFHKPR325/2024/04	SUPPLY & DELIVERY OF SAFI	Ahero, Kochogo-Kisumu
	LATRINE MATERIALS - As per	
	specification provided on RFQ	

Interested bidders must enclose the following documents:

- Valid KRA Pin/VAT/Tax Compliance certificate
- CR12
- Valid Business Permit
- Attachment of 3 similar works i.e. LPO's/Contracts
- At least 2-3 years of operation
- Price quoted should be inclusive of tax where applicable and transport cost to Ahero Kochogo Project Site.
- Company profile

Detailed request for quotation may be obtained (Free of charge) from Habitat for Humanity Kenya website: https://hfhkenya.org/tenders/

Duly completed and sealed tender documents in plain envelope with the tender number **HFHKPR325/2024/04** and title clearly indicated **(SUPPLY & DELIVERY OF SAFI LATRINE MATERIALS)** on the envelope should be deposited in the tender box placed at the **Habitat for Humanity Kenya** on or before **close** of business on 19th April 2024 at 5.00 p.m. addressed to;

The Chairperson, Procurement Committee, Habitat for Humanity Kenya Kasuku Lane-off Lenana Road, P.O Box 38948 – 00623, Nairobi Kenya.

Habitat for Humanity Kenya reserve the right to accept or reject any tender in part or wholly and does not bind itself to accept the lowest bidder. Only successful bidders will receive communication from HFHK office. Any form of canvassing either directly or indirectly shall lead to disqualification of the tender.

SAFI Latrine RFQ- SUPPLY OF MATERIALS IN KOCHOGO SOUTH, KISUMU COUNTY HFHK-Material Schedule

EM	DESCRIPTION	UNIT	QUANTITY	RATE (KSh)	AMOUNT (
-	SAFI Components		+		-
	Concrete Slab				
	Cement (50kg Bag) and water proof	No	1		
	Sand (Wheelbarrow)	No	2		
	Ballast - 1/2" - 1" (Wheelbarrow)	No	2		
	Reinforcement (D8)	No	2		
	Concrete Ring Cover Slab				
	Portlant Cement (50kg Bag) and water proof	No	1		
	Sand (Wheelbarrow)	No	1		
	Wire mesh (4ft by 8ft - Heavy)	No	1		
	Ballast - 1/2" - 1" (Wheelbarrow)	No	1		
	Squat Pan	140			
	Sand (Wheelbarrow)	No	1		
	Chicken wire	No	1		1
	Super Structure	INO			1
	Foundation and Walling	-			+
		No	220		-
	Bricks (11"x6"x4")	No	330		+
	Cement (50kg bag)	No	8		
	Sand (Wheelbarrow)	No	32		-
	Ballast - 1/2" - 1" (Wheelbarrow)	No	3		-
	Hoop iron	Kg	6		
	Reinforcement (D8)	No	1		
	Reinforcement (R6)	No	1		
	Formwork (Cypress Timber 6x1)	ft	12		
	Binding wire	Kg	1		
	Dump proof Membrane	m ²	2		
	Roof				
	Iron sheets (2m box profile blue in colour 30G)	No.	3		
-	Cypress Timber (Wall Plate - 4x2)	ft	16		
-	Cypress Timber (Rafters - 3x2))	ft	15		
	Cypress Timber (purlins - 2x2))	ft	15		
	Assorted Ordinary Nails (2", 3", 4")	kg	2		
	Roofing Nails	kg	1		
	Facial Board (6x1) cypress	ft	22		1
	Sub Total carried from the previous page			*	
1	Door				
- 10	Door shutter and frame	No	1		
_	Lock - Inside	No	1		
_	Lock - Outside	No	1		
	Paint				
_	Undercoat	Ltrs	6		
_	Plastic emulsion paint - soft white (vesta)	Ltrs	6		
	4" painting brush	No	1		
	Vent	140	- 1		
_	Vent pipe (20ft 4 inch PVC)	No	1		
-11	nsect mesh	m²	1		-
-					-
+					
-					
-		\perp			
\perp					
-					
		-	_		
-					
т	otal For One Latrine block	+	-		
_	otal For One Latrine block				