#### SAFI Latrine BOQ FOR SOLIO-Matrials supplied to 16 Households in Solio

ITEM		UNIT	QUANTITY(1)	QUANTITY (16)	RATE (KSh)	AMOUNT (KSh)
2	Concrete Ring		-			
2.1.1	Portlant Cement (50kg Bag) I/2 " Ballast(96 wheelbarrows)	No No	2 2	44 118		
2.1.2 2.1.3	Sand (48 Wheelbarrows)	No	3	62		
2.1.3	Wire mesh (4ft by 8ft)	No	6	96		
2.1.1		110	Ŭ	00		
2.2	Concrete Ring Cover Slab					
2.2.1	Cement (50kg Bag)	No	1	24		
2.2.2	ballast 1/2 (48 wheelbarrows)	No	1	72		
2.2.3	Sand (Wheelbarrow)	No	2	56		
2.2.4	Wire mesh (4ft by 8ft - Heavy)	No	1	16		
2.3	Concrete Ring Cover Slab					
2.3.1	Portlant Cement (50kg Bag)	No	1	24		
2.3.2	Sand (Wheelbarrow)	No	1	32		
-	,	-				
2.4	Squat Pan					
2.4.1	Sand (Wheelbarrow)	No	1	32		
2.4.2	Chicken wire	No	1	16		
3	Super Structure					
3.1	Foundation and Walling			10		
3.1.0	BRC (A142) (one roll for 16 latrines)	Roll	1	16		
3.1.1	Machine cut (5*8) Cement (50kg bag)	No No	80 10	1,280 160		
3.1.2 3.1.3	Sand (Wheelbarrow)	No	10	208		
3.1.4	Ballast - 1/2" - 1" (Wheelbarrow)	No	10	160		
3.1.5	Hoop iron	Kg	1	16		
3.1.6	Dump proof	m <sup>2</sup>	1	16		
3.1.7	Vent Block (300cm*200cm- behind the latrine)	No	2	32		
3.2	Roof	Na	2	20		
3.2.1 3.2.2	Iron sheets (2m) Cyprass Timber (Wall Plate - 3x2)	No. ft	2 15	32 240		
3.2.2	Cyprass Timber (Rafters - 3x2)	ft	15	240		
	Cyprass Timber (purlins - 2x2)	ft	20	320		
	Assorted Ordinary Nails (2", 3", 4") (4" 1kg, 3" 0.5kg 2" 0.5kg	kg	2	32		
3.2.6	Roofing Nails	kg	1	16		
3.2.7	Facial Board (6x1)	ft	20	320		
<b>3.3</b> 3.3.1	Door Door shutter and frame (pattern door 32*80)	No	1	16		
3.3.2	Lock - Inside	No	1	16		
3.3.3	Lock - Outside	No	1	16		
3.3.4	Hinges	Pair	2	32		
3.4	Paint					
3.4.1	Undercoat	Ltrs	20	20		
3.4.2	Plastic emulsion paint - soft white (vesta)	Ltrs	20	20		
	Paint Safaricom Green Paint Blue bird	Ltrs Ltrs	16 16	16 16		
	Black Paint	Ltrs	16	16		
	4" painting brush	No	1	16		
	Turpentine	ltrs	1	16		
3.5	Vent					
3.5.1	Vent pipe (20ft 4 inch PVC)(0.5 per latrine)	No	0.5	8		
3.5.2 3.5.3	Vent cap (4 inch PVC) Fly screen/Mosquito Gauze Mesh (0.25m x 0.25m)	Pcs	1	16 16		
3.5.3	1 y SUCENINOSQUILO GAUZE MESTI (U.2011 X U.2011)	Pcs		01		
		_				
						1
	•					

ITEM	DESCRIPTION	UNIT	QUANTITY(1)	QUANTITY (16)	RATE (KSh)	AMOUNT (KSh)
-		-				
	Total					-
	I Utai					-

# EVALUATION CRITERIA: SUPPLY OF CONSTRUCTION MATERIALS FOR MATERIALS FOR 16 SAFI RING LATRINES IN SOLIO LAIKIPIA COUNTY

### Stage 1: Preliminary Bid Responsiveness Assessment

These are mandatory documents to be attached to the tender document. Absence of any of these documents will lead to the bidder being disqualified and will not be considered proceed to the next stage of evaluation.

Item	Requirement	Yes / No
1.	Certificate of Registration/Incorporation.	
2.	Updated copy of certified CR12 Form	
3.	Current Single Business Permit	
4.	Valid KRA Tax Compliance Certificate	
5.	Priced Bill of Quantities.	
6.	Bank Statement (January – December 2024)	

# **Stage 2: Technical Evaluation Stage**

The technical evaluation is weighted out of 100 points with a pass mark of 70 points. Any bidder scoring 70 points and above in the technical evaluation will be considered for financial evaluation stage. Any bidder scoring below 70 Points in the Technical Evaluation will be disqualified from further evaluation.

	Particulars/Items	Max Points
1.	Experience in handling the same magnitude of work i.e. supply of construction materials. Attach at least 7 purchase order. <b>10 points</b> will be awarded for each relevant purchase order attached. i. Similar works, similar magnitude <b>-70 points</b>	70 points
3.	Work plan/Schedule. Provide a work plan detailing the duration the assignment will take <b>30 points</b>	30 points
	Total	100 points

# 3) Financial Evaluation Criteria

The bidders who pass the technical evaluation will be subjected to a tender price comparison.

HFHK will award the Contract to the tenderer whose tender is determined to be substantially responsive to the tender documents and who has offered the lowest evaluated tender price.